

Low Cost Interior Works

BOQ

S.No.	DESCRIPTION	QTY	UNIT
1.0	WOOD WORK- CUPBOARDS, KITCHEN AND VANITY		
a	<p>Providing and fixing modular kitchen with the shutters in 18 mm thick alternate hardwood commercial ply topped with 1mm thick laminate, inside of the cabinetry is finished with 18mm thick commercial ply with 0.8mm thick laminate(as/ selected shade from the catalogue). The kitchen to have three to 4 drawers and 2 deep drawers. The hardware shall include Channels,Handle etc (The rate doesnt not include any appliances like chimney, exhaust or dishwahr etc) The rate will vary is the above specifications are changed. These rates are based on the layout and final rates will depend upon the approved design of the kitchen by the client. All hardware, hinges, channels to be of EBCO Brand in SS finish.</p>	100	sft.
b	<p>Providing and fixing cupboards with the shutters in 18 mm thick alternate hardwood commercial ply finished with 1mm thick laminate(Local Brand) inside of the cabinetry is finished with 18m thick alterante hardwood commercial ply with 0.8mm thick laminate(as/ selected shade from the catalogue). The cupboards shall have two drawers, shelves and hanging rod. The hardware to include: handles (All hardware, hinges, channels to be of EBCO(Brand) make in SS finish. These rates apply to the above specification. If the client changes any specification then the rates shall vary accordingly</p>	400	sft.
c	<p>Providing and fixing bathroom vanity storage with the shutters in 18 mm thick alternate hardwood commercial ply finished with 1mm thick laminate, inside of the cabinetry is finished with 18m thick alterante hardwood commercial ply with 0.8mm thick laminate(as/ selected shade from the catalogue). The hardware to include: handles (All hardware, hinges, channels to be EBCO(Brand) in SS finish. These rates apply to the above specification. If the client changes any specification then the rates shall vary accordingly</p>	15	sft